

Just the Facts

WYNN HOSPITAL

Each week, "Just the Facts" provides information about a key aspect of the Wynn Hospital being built by Mohawk Valley Health System (MVHS). It is designed to keep our medical staff, employees and volunteers updated and to share with family, friends and neighbors so we keep our community informed about how we're transforming healthcare in our region.



TOPIC FOR TUESDAY, JANUARY 3, 2023:

Pre-assembled Door Hardware

The hardware on the doors in the Wynn Hospital will be pre-assembled prior to shipping to the jobsite for field installation. Hardware pre-assembled doors are wrapped/protected and set on pre-packaged skids to allow offloading with a pallet jack. Honeycomb cardboard spacers are used in between the door slabs to secure appropriate spacing to avoid damage and provide stack stability during shipment. All loose hardware that must be installed in the field such as strikes, pivots, floor/wall stops, surface sweeps, etc., are individually labeled and packaged on the top of each skid of doors associated with the hardware.

Pre-installed door hardware reduces the duration of overall door and hardware installation, including the time required for inventorying hardware on site. It also means off-site quality assurance/quality control since installation of the hardware by the door contractor allows the contractor to identify and address any discrepancies or wrong orders prior to shipping.

